



**PROCEEDINGS OF THE COCHIN DEVASWOM BOARD**  
Repairs and painting of Anjaneya guest house of Thiruvilwamala temple .

- Read 1. Note from AE dt. 08-11-2023  
2. Note from AEE dt. 20-11-2023  
3. Note from EE dt. 20-11-2023  
4. Decision of DC dt. 22-11-2023

Order on H1. 853/22 dt. 26-12-2023

As per the papers cited above an estimate of Rs. 4,50,000/- (Rupees Four lakh and fifty thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 04-01-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thiruvilwamala for exhibiting in their office Notice boards.

(By Order)


Sd/-

S. Gopakumar  
Assistant Engineer

To

✓ Notice Board, AC- Thiruvilwamala  
CA to DC, EE, AEE, AE,  
S.F,

//Approved for issue//

  
Junior Superintendent

TS Register No: 3207/2023-2024

AS Register No:3383/2023-2024

Repairs and painting of Anjaneya Guest house of Thiruvilwamala temple

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Painting	
1	od225760/2023_2024 Dismantling and removing Mangalore tiles over roofs including ridges, hips, valley sheets, wind ties and bordering but excluding roof timber and stacking materials within a distance of 150m
Net Total Quantity	
131.600 sqm	
Say 131.600 sqm @ Rs 878.78 / sqm	
<b>Rs 115647.45</b>	
2	15.31 Dismantling tiled roofing with battens, boarding etc. complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.
Net Total Quantity	
44.000 sqm	
Say 44.000 sqm @ Rs 176.54 / sqm	
<b>Rs 7767.76</b>	
3	od226058/2023_2024 supplying and new fixing Anjily wood reapers of size 50mm x 25mm with wire nails including cost and and conveyance of materials etc. complete.
Net Total Quantity	
0.205 cum	
Say 0.205 cum @ Rs 108923.21 / cum	
<b>Rs 22329.26</b>	
4	od226074/2023_2024 Supplying and stacking M.P ridge tile including cost and conveyance charge etc complete
Net Total Quantity	
60.000 each	
Say 60.000 each @ Rs 45.30 / each	
<b>Rs 2718.00</b>	
5	od226075/2023_2024 Supplying and stacking M.P Roofing tile including cost and conveyance charge etc complete
Net Total Quantity	
500.000 each	
Say 500.000 each @ Rs 31.36 / each	
<b>Rs 15680.00</b>	
6	od226076/2023_2024 Roofing with existing MP tiles including labour charges etc. complete. 
Net Total Quantity	
175.500 sqm	
Say 175.500 sqm @ Rs 69.85 / sqm	
<b>Rs 12258.68</b>	
7	od226077/2023_2024 Setting M.P hip and ridge tiles set in lime mortar 1:2 including finishing edges including all cost of materials labour charges and conveyance charges etc. complete.
Net Total Quantity	
30.100 metre	