



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Providing drainage facility from Sreekovil at Ponjanam temple.

- Read
1. Note from AE dt. 05-06-2023
 2. Note from AEE dt. 08-06-2023
 3. Note from EE dt. 08-06-2023
 4. Decision of DC dt. 12-06-2023

Order on H1. 924/2023 dt. 13-06-2023

As per the papers cited above an estimate of Rs. 1,30,000/- (Rupees One lakh and thirty thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 20-06-2023 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification are herewith forwarded to Special Devaswom commissioner Devaswom Assistant Commissioner, Thiruvanchikulam for exhibiting in their office Notice boards .

(By Order)


Sd/-

M.K. Dileep
Assistant Engineer

To

Notice Board,
AC – Thiruvanchikulam,
CA to DC, EE, AEE, AE, HD, S.F,

//Approved for issue//


(LDC)
For Junior Superintendent

TS Register No: 704/2023-2024

AS Register No:730/2023-2024

Providing drainage facility from sreekovil at Ponjanam temple

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Dismantling	
1	od73294/2023_2024 Clearing and disposal of debris away from site Labour- Mate
Net Total Quantity 15.000 Day	
Say 15.000 Day @ Rs 971.70 / Day Rs 14575.50	
2 Manhole	
1	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil
Net Total Quantity 5.000 cum	
Say 5.000 cum @ Rs 214.03 / cum Rs 1070.15	
2	50.6.2.1 Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete
Net Total Quantity 2.550 cum	
Say 2.550 cum @ Rs 6237.61 / cum Rs 15905.91	
3	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)
Net Total Quantity 0.500 cum	
Say 0.500 cum @ Rs 7367.55 / cum Rs 3683.78	
3 PVC pipe work	
1	50.18.9.9.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of Joints complete as per direction of engineer in charge. 110 mm dia 6Kg/cm2
Net Total Quantity 130.000 metre	
Say 130.000 metre @ Rs 526.17 / metre Rs 68402.10	
Service Tax @ 18.0%	
Service Tax Amount 18654.74	

Total with Service Tax Amount	122291.74
Lumpsum for round off	7708.26
TOTAL Rs 130000.00	
Rounded Total Rs 1,30,000	
Rupees One Lakh Thirty Thousand Only	

(Cost Index Applied for this estimate is 35.59%)



Other Engineering Organisations

PRICE

