



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Renovation of south side toilets at Thriprayar temple – Thriprayar Devaswom Thrissur group.

- Read
1. Report of DAC Thrissur on R1. 5670/22 dt. 25-01-2024
 2. Note from AE dt. 10-05-2024
 3. Note from AEE dt. 13-05-2024
 4. Note from EE dt. 13-05-2024
 5. Decision of DC dt. 15-05-2024

Order on H1. 991/2024 dt. 17-05-2024

As per the papers cited above an estimate of Rs. 4,80,000/- (Rupees Four lakh and eighty thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 24-05-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)

Sd/-

M.K. Dileep

Assistant Engineer

To

Notice Board, AC- Thrissur,
CA to DC, EE, AEE, AE,S.F,

//Approved for issue//

Junior Superintendent

Renovation of south side toilets at Thriprayar temple

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Renovation of toilets	
1	15.2.1 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)
Net Total Quantity	
16.920 cum	
Say 16.920 cum @ Rs 2045.12 / cum	
Rs 34603.43	
2	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)
Net Total Quantity	
1.692 cum	
Say 1.692 cum @ Rs 7367.55 / cum	
Rs 12465.89	
3	11.40 Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in all colours, shades, except white, Ivory, Grey Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete.
Net Total Quantity	
16.920 sqm	
Say 16.920 sqm @ Rs 1378.00 / sqm	
Rs 23315.76	
4	8.31 Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.
Net Total Quantity	
90.420 sqm	
Say 90.420 sqm @ Rs 1212.78 / sqm	
Rs 109659.57	
5	17.2.1 Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid
Net Total Quantity	
8.000 each	