



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Repairing of LT panel installed at West Gopuram of Wadakkunnathan temple

- Read
1. Note from AE (Electrical) dt. 03-02-2024
 2. Note from AEE dt. 07-02-2024
 3. Note from EE dt. 07-02-2024
 4. Decision of DC dt. 08-02-2024

Order on H1. 07/2024 dt. 16-02-2024

As per the papers cited above an estimate of Rs. 53,993/- (Rupees Fifty three thousand nine hundred and ninety three only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 22-02-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)

Sd/-

V.K. Ramakrishnan
Assistant Engineer (Electrical)

To

✓ Notice Board, AC- Thrissur,
CA to DC, EE, AEE, AE (Electrical),
S.F,

//Approved for issue//

Junior Superintendent

Repairing of the existing LT Panel at Vadakkumnathan Temple.

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 DB		
1	od319419/2023_2024 Supply of 10SWG pure bare copper wire @ 7381/100 mts	
	Net Total Quantity	10.000 per metre
	Say 10.000 per metre @ Rs 58.29 / per metre	Rs 582.90
2	od320442/2023_2024 Repairing of the existing LT Panel at Vadakkumnathan Temple, Thrissur	
	Net Total Quantity	1.000 no
	Say 1.000 no @ Rs 35658.05 / no	Rs 35658.05
3	90.6.6.7 Supply and drawing FRLS PVC insulated & sheathed 650/1100 V grade 3 core copper conductor flat cable for submersible pump motor conforming to IS 694 part I 1990 as required including giving necessary connections of the following sizes.25 sq mm	
	Net Total Quantity	10.000 metre
	Say 10.000 metre @ Rs 808.27 / metre	Rs 8082.70
4	od322245/2023_2024 Dismantling the damaged FFU from the existing LT Panel without and damage to the Board ,of any size.	
	Net Total Quantity	5.000 each
	Say 5.000 each @ Rs 286.76 / each	Rs 1433.80
	Provision for GST payments (in %) @	18.0%
	Amount reserved for GST payments	8236.34
	Total	53993.34
	Lumpsum for round off	0.00
		TOTAL Rs 53993.34
		Rounded Total Rs 53,993
		Rupees Fifty Three Thousand Nine Hundred and Ninety Three Only

(Cost Index Applied for this estimate is 35.59%)