



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Abstract

Cochin Devaswom Board – Maramath wing- Repairs to main comfort station and D.T.P.C comfort station at Chottanikkara Bhagavathy temple Quotations invited – Order issued

- Read
1. Note from AE dt. 09-10-2024
 2. Note from AEE dt. 15-10-2024
 3. Note from EE dt. 15-10-2024
 4. Decision of DC dt. 15-10-2024

Order on H1. 2013/2024 dt. 15-10-2024

As per the papers cited above an estimate of Rs. 4,98,000/- (Rupees Four lakh and ninety eight thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 23-10-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Chottanikkara for exhibiting in their office Notice boards.

(By Order)

Sd/-

D. Suni

Assistant Executive Engineer

To

~~Notice Board,~~
The Assistant Commissioner - Chottanikkara,
The Devaswom Commissioner,
The Executive Engineer ,
The Assistant Executive Engineer,
The Assistant Engineer, Stock File

//Approved for issue//

[Signature]
Junior Superintendent

for Senior clerk

TS Register No: 1650/2024-2025

AS Register No:1701/2024-2025

Repairs to Main comfortstation and D.T.P.C comfort station At Chottanikkara
Bhagavathy Temple

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Repairs		
1	od144614/2024_2025 Extra Labors for Mate	
		Net Total Quantity 1.000 Day
		Say 1.000 Day @ Rs 971.70 / Day Rs 971.70
2	od144615/2024_2025 Extra Labors Mason (brick layer) 1st class	
		Net Total Quantity 1.000 Day
		Say 1.000 Day @ Rs 1162.26 / Day Rs 1162.26
3	14.1.1 Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead:With cement mortar 1:4 (1 cement : fine sand)	
		Net Total Quantity 75.000 sqm
		Say 75.000 sqm @ Rs 491.78 / sqm Rs 36883.50
4	17.2.2 Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:W.C. pan with ISI marked black solid plastic seat and lid	
		Net Total Quantity 1.000 each
		Say 1.000 each @ Rs 6050.91 / each Rs 6050.91
5	14.82 Dismantling W.C. Pan of all sizes including disposal of dismantled materials/c malba all complete as per directions of Engineer-in-Charge	
		Net Total Quantity 4.000 no
		Say 4.000 no @ Rs 113.01 / no Rs 452.04
6	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	