



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Abstract

Cochin Devaswom Board – Maramath wing- Providing interlock tiles over west 'Nada' dismantled banyan tree area and toilet pathway of Nelluvai Dhanwanthari temple – Nelluvai Devaswom – Thiruvilwamala Group- Quotations invited – Order issued

- Read
1. Note from AE dt. 07-10-2024
 2. Note from AEE dt. 08-10-2024
 3. Note from EE dt. 08-10-2024
 4. Decision of DC dt. 09-10-2024

Order on H1. 1999/2024 dt. 10-10-2024

As per the papers cited above an estimate of Rs. 4,24,000/- (Rupees Four lakh and twenty four thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 21-10-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thiruvilwamala group for exhibiting in their office Notice boards.

(By Order)

Sd/-

S. Gopakumar

Assistant Engineer

To

✓ Notice Board,

The Assistant Commissioner - Thiruvilwamala,
The Devaswom Commissioner, The Executive Engineer ,
The Assistant Executive Engineer,
The Assistant Engineer, Stock File

//Approved for issue//


Junior Superintendent

TS Register No: 1624/2024-2025

AS Register No:1673/2024-2025

Providing Interlock tiles over west 'Nada',dismantled banyan tree area and toilet pathway of Nelluvai Dhanwantharai Temple- Nelluvai Devaswom-Thiruvilwamala

group

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

| 1 Earth work | |
|--|---|
| 1 | 2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil |
| Net Total Quantity | |
| 60.000 cum | |
| Say 60.000 cum @ Rs 214.03 / cum | |
| Rs 12841.80 | |
| 2 Interlocktiles | |
| 1 | 16.68 Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. |
| Net Total Quantity | |
| 342.000 sqm | |
| Say 342.000 sqm @ Rs 1011.57 / sqm | |
| Rs 345956.94 | |
| Provision for GST payments (in %) @ | |
| 18.0% | |
| Amount reserved for GST payments | |
| 64583.77 | |
| Total | |
| 423382.77 | |
| Lumpsum for round off | |
| 617.23 | |
| TOTAL Rs 424000.00 | |
| Rounded Total Rs 4,24,000 | |
| Rupees Four Lakh Twenty Four Thousand Only | |

(Cost Index Applied for this estimate is 35.59%)