



## PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

### Abstract

Cochin Devaswom Board – Maramath wing- Constructing toilet block at Sree Karkidakathukavu temple– Karumarakkad Devaswom – Thiruvilwamala Group-  
Quotations invited – Order issued

- Read
1. Note from AE dt. 26-07-2024
  2. Note from AEE dt. 06-08-2024
  3. Note from EE dt. 06-08-2024
  4. Decision of DC (incharge) dt. 08-08-2024

Order on H1. 1228/2023 dt. 03-09-2024

As per the papers cited above an estimate of Rs. 2,35,000/- (Rupees Two lakh and thirty five thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 10-09-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.


A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thiruvilwamala group for exhibiting in their office Notice boards.

(By Order)  
Sd/-  
S. Gopakumar  
Assistant Engineer

To

Notice Board,  
The Assistant Commissioner - Thiruvilwamala,  
The Devaswom Commissioner, The Executive Engineer ,  
The Assistant Executive Engineer,  
The Assistant Engineer, Stock File

//Approved for issue//

  
for Junior Superintendent  
Senior clerk

TS Register No: 1925/2023-2024

AS Register No:2030/2023-2024

**Constructing toilet block at Karkidakathukavu temple,Karumarakkad**  
**Devaswom,Thiruvilwamala Group**

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

<b>1 Earthwork</b>	
1	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil
Net Total Quantity	
12.186 cum	
Say 12.186 cum @ Rs 214.03 / cum	
<b>Rs 2608.17</b>	
<b>2 Random rubble</b>	
1	7.1.1 Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with:Cement mortar 1:6 (1 cement : 6 coarse sand)
Net Total Quantity	
5.009 cum	
Say 5.009 cum @ Rs 7204.78 / cum	
<b>Rs 36088.74</b>	
<b>3 Solid block</b>	
1	50.6.2.2 Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in : CM 1:6 ( 1 cement : 6 coarse sand) etc complete
Net Total Quantity	
3.600 cum	
Say 3.600 cum @ Rs 6984.85 / cum	
<b>Rs 25145.46</b>	
<b>4 concrete</b>	
1	5.3 Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15 <sup>0</sup> landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) : 3 graded stone aggregate 20 mm nominal size).
Net Total Quantity	
0.844 cum	
Say 0.844 cum @ Rs 11492.88 / cum	
<b>Rs 9699.99</b>	
<b>5 Centering shuttering</b>	