



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Abstract

Cochin Devaswom Board – Maramath wing- Constructing Vazhipadu counter near Koothambalam – Wadakkunnathan temple – Wadakkunnathan Devaswom - Quotations invited – Order issued.

- Read
1. Order on C.S 8832/2023 dt. 02-12-2023
 2. Note from AE dt. 20-06-2024
 3. Note from AEE dt. 26-06-2024
 4. Note from EE dt. 26-06-2024
 5. Decision of DC dt. 27-06-2024

Order on H1. 1291/2024 dt. 01-07-2024

As per the papers cited above an estimate of Rs. 3,43,000/- (Rupees Three lakh and forty three thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 08-07-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur group for exhibiting in their office Notice boards.

(By Order)

Sd/-


K. Sreeja

Assistant Engineer

To

~~Notice Board,~~
The Assistant Commissioner - Thrissur,
The Devaswom Commissioner, The Executive Engineer ,
The Assistant Executive Engineer,
The Assistant Engineer, Stock File

//Approved for issue//

for 
Junior Superintendent
Senior clerk

TS Register No: 678/2024-2025

AS Register No:678/2024-2025

**Constructing vazhyapad counter near Koothambalam -Wadakumnathan Temple-
Wadakumnathan Devaswom -Thrissur Group**

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Vazhyapad counter		
1	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	
Net Total Quantity		358.901 kilogram
Say 358.901 kilogram @ Rs 101.29 / kilogram		Rs 36353.08
2	21.1.1.2 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately):For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	
Net Total Quantity		91.390 kg
Say 91.390 kg @ Rs 537.07 / kg		Rs 49082.83
3	21.1.2.2 For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	
Net Total Quantity		13.483 kg
Say 13.483 kg @ Rs 643.10 / kg		Rs 8670.92
4	21.3.1 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness	
Net Total Quantity		23.710 sqm
Say 23.710 sqm @ Rs 1176.65 / sqm		Rs 27898.37
5	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	