



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Abstract

Cochin Devaswom Board – Maramath wing- Electrical estimate for providing drinking water for elephants at Kokarny Parambu, Wadakkunnathan temple - Quotations invited – Order issued

- Read
1. Note from AE(Electrical) dt. 04-12-2024
 2. Note from AEE dt. 06-12-2024
 3. Note from EE dt. 06-12-2024
 4. Decision of DC dt. 11-12-2024

Order on H1. 2406/2024 dt. 16-12-2024

As per the papers cited above an estimate of Rs. 79,000/- (Rupees Seventy nine thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 24-12-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)

Sd/-

V.K. Ramakrishnan

Assistant Engineer (Electrical)

To

✓ Notice Board,
The Assistant Commissioner, Thrissur,
The Executive Engineer,
The Assistant Executive Engineer,
The Assistant Engineer, Stock File

//Approved for issue//

APK
for. Junior Superintendent

Senior clerk

TS Register No: 2406/2024-2025

AS Register No:2445/2024-2025

Estimate for providing Drinking water at Kokkarny parambu at Vadakunathan Temple.

Detailed Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

| SI No | Description | No | L | B | D | CF | Quantity | Remark |
|-----------------|---|----|---|---|---|----|-------------------------------------|--------------------|
| 1 Wiring | | | | | | | | |
| 1 | 2.3.3 Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCBIRCCB/Isolator12 way, Double door | 1 | | | | | 1.000 | |
| | | | | | | | Total Quantity | 1.000 each |
| | | | | | | | Total Deducted Quantity | 0.000 each |
| | | | | | | | Net Total Quantity | 1.000 each |
| | | | | | | | Say 1.000 each @ Rs 2440.62 / each | Rs 2440.62 |
| 2 | od180040/2024_2025 Supply of 1.5 HP 38 mm delivery Open well submersible Pump with Strainer, Bend pipe, S S Hose color Panel etc.(Make:- Aquatex / Kirloskar / or equivalent .) | 1 | | | | | 1.000 | |
| | | | | | | | Total Quantity | 1.000 each |
| | | | | | | | Total Deducted Quantity | 0.000 each |
| | | | | | | | Net Total Quantity | 1.000 each |
| | | | | | | | Say 1.000 each @ Rs 27923.81 / each | Rs 27923.81 |
| 3 | 2.10.1 Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole | 8 | | | | | 8.000 | |
| | | | | | | | Total Quantity | 8.000 each |
| | | | | | | | Total Deducted Quantity | 0.000 each |
| | | | | | | | Net Total Quantity | 8.000 each |
| | | | | | | | Say 8.000 each @ Rs 237.28 / each | Rs 1898.24 |
| 4 | 2.12.1 Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete | | | | | | | |